

क्षेत्रीय कार्यालय, म.प्र.प्रदूषण नियंत्रण बोर्ड

दीन दयाल नगर, हाऊसिंग बोर्ड कॉलोनी, सागर

Telefax-07582-263774, E-mail-romppcb\_sagar@rediffmail.com

निविदा आमंत्रण सूचना

क्रमांक 1836 /क्षे.का./प्रनिबो/15-16

सागर, दिनांक 30/11/15


मध्यप्रदेश के राज्यपाल की ओर से अधोहस्ताक्षरकर्ता के कार्यालय में पृथक-पृथक मोहरबंद निविदायें प्रपत्र 'ए' प्रतिशत दर पर निम्नलिखित कार्य हेतु प्रमुख अभियंता, लोक निर्माण विभाग भोपाल के यूनीफाइड एस.ओ.आर. दिनांक 1.8.2014 से प्रभावशील (निविदा जारी तक संशोधन) पर केन्द्रीयकृत व्यवस्था के अन्तर्गत लोक निर्माण विभाग भोपाल के अन्तर्गत "सी श्रेणी अथवा उच्च श्रेणी में पंजीकृत /अनुभवी ठेकेदारों से अधोहस्ताक्षरकर्ता के कार्यालय में दिनांक 29.12.2015 को अपराह्न 3:00 बजे तक आमंत्रित की जाती है। प्राप्त निविदायें दिनांक 29.12.2015 को अपराह्न 4:30 बजे उपस्थित निविदाकारों या उनके द्वारा अधिकृत प्रतिनिधियों के समक्ष खोली जावेगी। कोरे निविदा प्रपत्र दिनांक 28.12.2015 तक कार्यालयीन समय में क्षेत्रीय कार्यालय, म.प्र. प्रदूषण नियंत्रण बोर्ड सागर से निर्धारित मूल्य जमा करने पर क्रय किये जा सकते हैं।

कार्य का विवरण- क्षेत्रीय कार्यालय सागर के कार्यालयीन भवन के संधारण एवं अन्य कार्य के निर्माण कार्य ( निर्धारित शेड्यूल अनुसार ) बावत।

क्र.	अनु. लागत	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्य की समाप्ति- वर्षाकाल सहित
1	25.63 लाख	51,500/-	रु. 5000/-	कार्यादेश जारी दिनांक से 4 माह

- (1) निविदायें इस निविदा सूचना के पैरा में वर्णित पात्र ठेकेदारों से ही प्राप्त की जावेगी। यदि किसी अपात्र ठेकेदार द्वारा निविदा प्रस्तुत की जाती है तो ऐसी निविदा पर विचार नहीं किया जावेगा एवं ऐसे ठेकेदार द्वारा जमा की गई अर्नेस्ट मनी जप्त मानी जावेगी।
- (2) यह केवल संक्षिप्त निविदा सूचना है। कार्य का विस्तृत विवरण जैसे ड्राइंग-डिजाइन स्पेशीफिकेशन तथा कार्य की विस्तृत शर्तें कार्यालयीन समय के दौरान निविदा प्राप्ति से एक दिन पूर्व तक संबंधित कार्यालय में ठेकेदारों द्वारा देखी जा सकेगी।
- (3) शासन द्वारा निर्धारित टेक्स ठेकेदार को देना होगी।
- (4) रायल्टी आदि ठेकेदार को देना होगी।
- (6) निविदा की दरों की वैधता 120 दिन तक रहेगी।
- (7) सशर्त निविदा मान्य नहीं होगी।
- (8) धरोहर राशि के बिना निविदायें मान्य नहीं की जावेगी। धरोहर राशि एफ.डी.आर./डी.डी. जो कि सदस्य सचिव म.प्र. प्रदूषण नियंत्रण बोर्ड भोपाल कार्यालय के नाम से देय होगी।


- (9) सक्षम अधिकारी को अधिकार होगा कि सभी निविदाओं को बिना कारण बताये अस्वीकृत/स्वीकृत कर सकता है।
- (10) अनुबंध के पूर्व 5% परफारमेंस सिक्यूरिटी राशि जमा करना अनिवार्य होगा।
- (11) कार्य के दौरान किसी हानि एवं दुर्घटना की जिम्मेदारी ठेकेदार की ही होगी।
- (12) कार्य लक्ष्य एवं आवंटन की उपलब्धता के आधार पर आवंटित किया जावेगा।
- (13) शासन के नियमानुसार आयकर कटौती, वाणिज्य कर कटौती लेबर वेलफेयर कटौती देयको से की जावेगी।
- (14) कार्य स्थल पर सावधानी सूचना संकेत का उपयोग ठेकेदार को स्वयं के व्यय पर करना आवश्यक होगा।
- (15) कार्य इस कार्यालय की स्वीकृति के बिना सबलेटिंग नहीं किया जावेगा।
- (16) उपरोक्त कार्य निर्धारित समयावधि में ही पूर्ण किया जाना है। अतः निर्धारित समयावधि में कार्य पूर्ण करना अनिवार्य होगा।
- (17) निर्माणाधीन कार्य के दौरान आवश्यकतानुसार कार्य की मात्रा में कमी परिवर्तन अथवा अतिरिक्त कार्य विभाग द्वारा करवाया जा सकता है, जिसके लिये ठेकेदार बाध्य होगा।
- (18) म.प्र. शासन लोक निर्माण विभाग के पत्र क्रमांक F-53/2/2011/5788, भोपाल दिनांक 25/10/2011 में दिये गये निर्देशानुसार एस.ओ.आर. दर से 10 प्रतिशत अधिक नीचे (More Than 10% Below) होने पर निविदा दर को अव्यवहारिक दर माना गया है अतः म.प्र. शासन द्वारा दिये गये निर्देशानुसार अव्यवहारिक दर प्राप्त होने पर अतिरिक्त परफारमेंस गारंटी की राशि अनुबंध करने के पूर्व एफ.डी.आर. के रूप में जमा करनी होगी।
- (19) निविदा संबंधी जानकारी विभाग की वेबसाइट [www.mppcb.nic.in](http://www.mppcb.nic.in) देखी जा सकती है।

  
क्षेत्रीय अधिकारी,  
म.प्र. प्रदूषण नियंत्रण बोर्ड सागर

पृ0 क्रमांक /क्ष.का/प्रनिबो/2015/सागर  
प्रतिलिपि:-

दिनांक

- (1) सदस्य सचिव महोदय, म.प्र. प्रदूषण नियंत्रण बोर्ड, पर्यावरण परिसर, ई 5 अरेरा कोलोनी भोपाल।
- (2) अधीक्षण यंत्री (वित्त) मध्यप्रदेश प्रदूषण नियंत्रण बोर्ड, भोपाल
- (3) अधीक्षण यंत्री (प्रभारी प्रोजेक्ट शाखा) मध्यप्रदेश प्रदूषण नियंत्रण बोर्ड, भोपाल
- (4) कार्यपालन यंत्री, लोक निर्माण विभाग सागर
- (5) नोटिस बोर्ड

  
क्षेत्रीय अधिकारी,  
म.प्र. प्रदूषण नियंत्रण बोर्ड सागर

**NIT SCHEDULE FOR RENOVATION REPAIRING AND COLOUR WASHING  
WHITE WASHING WORK OF MP STATE POLLUTION DEPARTMENT  
BUILDING AT SAGAR**

No.	Item	Rate	Unit
1.	<p><b><u>S.O.R. Item No. 15.11.2 Page 272</u></b></p> <p>Dismantling tile/ Kota stone/ Marble / Granite work in floors/walls and roofs laid in cement mortar including stacking material within 50 metres lead.</p> <p>2Nox26.90x4.50 = 242.10</p>	26.00	Sqm
2.	<p><b><u>S.O.R. Item No. 15.2 Page 271</u></b></p> <p>Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge.</p>	356.00	Sqm
	15.2.2 Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix).		
3.	<p><b><u>S.O.R. Item No. 15.48 Page 276</u></b></p> <p>Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.</p>	13.00	sqm
4.	<p><b><u>S.O.R. Item No. 4.2 Page 45</u></b></p> <p>Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. up to floor two level, excluding the cost of centering, shuttering and finishing :</p>		
	4.2.1 With 20mm nominal size graded stone aggregate		

No.	Item	Rate	Unit
	4.2.1.4 Nominal Mix -1 Cement : 3 sand : 6 graded stone aggregate (M 10)	4134.00	Cum
5.	<p><b><u>S.O.R. Item No. 5.2 Page 65</u></b></p> <p>Reinforced cement concrete work (with 20mm nominal size graded stone aggregate) in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, posts and struts etc. above plinth level and up to floor two level excluding cost of centering, shuttering, finishing and reinforcement :</p>		
	5.2.1 M 20 —Grade Concrete	5202.00	Cum
6.	<p><b><u>S.O.R. Item No. 6.5 Page 85</u></b></p> <p>Brick work with well brunt open bhatta, bricks, crushing strength not less than 25kg /cm<sup>2</sup> and water absorption not more than 20% in foundation and plinth i/c curing etc complete.</p>		
	6.5.1 Cement mortar 1:4 (1 cement : 4 sand)	4347.00	Cum
7.	<p><b><u>S.O.R. Item No. 7.30 Page 107</u></b></p> <p>30mm red sand stone sun-shade (chisel-dressed) supported on red sand stone brackets, fixed in walls with cement mortar 1:4 (1 cement : 4 sand) including finishing complete.</p>	891.00	Sqm
8.	<p><b><u>S.O.R. Item No. 10.15 Page 181</u></b></p> <p>Steel work in built up tubular ( round, square or rectangular hollow tubes etc.) trusses/frame work etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.</p>		
	10.15.1 Hot finished welded type tubes	107.85	Kg

No.	Item	Rate	Unit
9.	<p><b><u>S.O.R. Item No. 12.17 Page 220</u></b></p> <p>Providing and fixing UV stabilised fibreglass reinforced plastic sheet roofing upto any pitch including fixing with polymer coated 'J' or 'L' hooks, bolts and nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% Ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.</p>		
	12.17.1 2mm thick corrugated (2.5" or 4.2" or 6") or step-down (2" or 3" or 6") as specified.	1031.00	Sqm
10.	<p><b><u>S.O.R. Item No. 13.41 Page 248</u></b></p> <p>Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, Like birla white /JK white or equivalent, over the plastered wall surface to prepare the surface even and smooth i/c all cost of material, labour and scaffold etc in all position complete.</p>	74.00	Sqm
11.	<p><b><u>S.O.R. Item No. 11.52 Page 205</u></b></p> <p>Providing and laying rectified Glazed Ceramic wall tiles 300x450 mm or more (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 12 mm thick Cement Mortar 1:3 (1 Cement : 3 sand) including pointing the joints with white cement and matching pigments etc., complete.</p>	1044.00	Sqm

No.	Item	Rate	Unit
12.	<p><b><u>S.O.R. Item No. 11.55 Page 206</u></b></p> <p>Providing and laying Vitrified tiles in floor with different sizes, with water absorption less than 0.08% and conforming to IS:15622 , of approved brand and manufacturer in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately).</p>		
	11.55.2 Size of Tile 600x600x9-10 nun		
13.	<p><b><u>S.O.R. Item No. 13.68 Page 252</u></b></p> <p>Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :</p>		
	13.68.1 Two or more coats on new work	53.00	Sqm
14.	<p><b><u>S.O.R. Item No. 17.4 Page 290</u></b></p> <p>Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.O pan) with seat and lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40nun flush bend, 20nun over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :</p>		
	17.4.1 White vitreous china dual purpose WC pan with white solid plastic seat and lid with 10 liter low level flushing cistern i/c C.P. flush bend.	5120.00	Each
15.	<p><b><u>S.O.R. Item No. 17.8 Page 292</u></b></p> <p>Providing and fixing one piece construction white</p>		

No.	Item	Rate	Unit
	vitreous china squatting plate with an integral longitudinal flushing pipe, white P.V.C. automatic flushing cistern, with fittings, standard size G.I. / PVC flush pipe for back and front flush with standard spreader pipes with fittings, G.I clamps and C.P. brass coupling complete including painting of fittings and cutting and making good the walls and floors etc. wherever required :		
	17.8.2 Range of two squatting plates with 5 litre P.V.C. automatic flushing cistern.	5128.00	Each
16.	<p><b><u>S.O.R. Item No. 17.14.1 Page 293</u></b></p> <p>Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS 13983 with C.I. brackets and stainless steel plug 40 mm including painting of fittings and brackets, cutting and making good the walls wherever required :</p>		
	17.14.1 Kitchen sink with drain board		
	17.14.1.1510x1040 mm bowl depth 250mm.	8074.00	Each
17.	<p><b><u>S.O.R. Item No. 17.11 Page 292</u></b></p> <p>Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require :</p>		
	17.11.8 White Vitreous China Surgeon type wash basin of size 660x460 mm with a pair of 15 mm C.P. brass pillar taps with elbow operated lever ISI marked.	3761.00	Each
18.	<p><b><u>S.O.R. Item No. 17.27 Page 295</u></b></p> <p>Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350mm.</p>	2243.00	Each

No.	Item	Rate	Unit
19.	<p><b><u>S.O.R. Item No. 18.10 Page 317</u></b></p> <p>Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc.</p> <p>Internal work - Exposed on wall</p>		
	18.10.1 15 mm dia. nominal bore	211.00	metre
	18.10.2 20 mm dia. nominal bore	255.00	metre
	18.10.3 25 mm dia. nominal bore	300.00	metre
20.	<p><b><u>S.O.R. Item No. 18.52 Page 330</u></b></p> <p>Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931</p>		
	18.52 115 mm nominal bore.	458.00	Each
21.	<p><b><u>S.O.R. Item No. 18.51 Page 330</u></b></p> <p>Providing and fixing brass stop cock of approved quality :</p>		
	18.51.2 20 mm nominal bore	344.00	Each
22.	<p><b><u>S.O.R. Item No. 19.4 Page 340</u></b></p> <p>Providing and laying below ground unplasticised PVC pipe to with stand working pressure of 4 kg/cm<sup>2</sup> solid waste pipes confirming to IS:13592 and IS:4985 including jointing with seal ring confirming to IS :5282 leaving 10mm gap for thermal expansion all necessary fittings etc. complete. Excavation to be paid seperately.</p>		
	19.4.1 110 mm diameter OD	234.00	Each
23.	<p><b><u>S.O.R. Item No. 13.5 Page 244</u></b></p> <p>15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement</p>		



No.	Item	Rate	Unit
	of mix :		
	13.5.1 1:3 (1 cement : 3 sand)	186.00	Sqm
24.	<p><b><u>S.O.R. Item No. 13.4 Page 244</u></b></p> <p>12 mm cement plaster finished with a floating coat of neat cement of mix :</p>		
	13.4.1 1:3 (1 cement : 3 sand)	164.00	Sqm
25.	<p><b><u>S.O.R. Item No. 21.11 Page 364</u></b></p> <p>Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side having 12 mm air gap including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant ) etc. as per specifications, drawings and direction of Engineer-in-charge complete.</p>	3473.00	Sqm
26.	<p><b><u>S.O.R. Item No. 12.53 Page 230</u></b></p> <p>Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false</p>		

No.	Item	Rate	Unit
	ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.		
	12.53.1 8 mm thick fully perforated calcium silicate board made with Calcareous and Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process to give stable crystalline structure with minimum compressive strength 225 kg/ sq. cm, bending strength 100 kg/sq. cm, of size 595x595 mm, having perforation of dia. 10 mm with minimum perforated area 18 % with non woven tissue on the back side, having an NRC ( Noise Reduction Coefficient) of 0.85, with 50 mm thick rockwool of 48 kg /cum backing.	1255.00	Sqm
27.	<b><u>S.O.R. Item No. 25.40 Page 395</u></b> Providing and fixing in position best indian Auto Closing Urinal valve open type (with DECOL cartredge) for urinal use only.	2400.00	Each
28.	<b><u>S.O.R. Item No. 25.43 Page 395</u></b> Providing and fixing in position best indian Auto Closing 40nun Flush valve (for W. C. European and Wall Hung Type) consealed type (with DECOL technology/cartredge).	3600.00	Each

No.	Item	Rate	Unit
29.	<p><b><u>S.O.R. Item No. 13.51 Page 249</u></b></p> <p>Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.</p>		
	13.51.2 Two coats.	56.00	Sqm
30.	<p><b><u>S.O.R. Item No. 21.3 Page 363</u></b></p> <p>Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) :</p>		
	21.3.1 With float glass panes of 4.0 mm thickness.	849.00	Sqm
31.	<p><b><u>S.O.R. Item No. 17.74 Page 304</u></b></p> <p>Providing and fixing CP brass towel ring of approved quality and make</p>		
	17.74.1 200mm dia ring	679.00	Each
32.	<p><b><u>S.O.R. Item No. 17.75 Page 304</u></b></p> <p>Providing and fixing CP brass soap dish of approved quality and make.</p>	422.00	Each
33.	<p><b><u>S.O.R. Item No. 17.68 Page 303</u></b></p> <p>Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shape with 6 mm thick hard board backing :</p>		
	17.68.4 Rectangular shape 1500x450 mm	1311.00	Each
34.	<p><b><u>S.O.R. Item No. 11.49 Page 205</u></b></p>	961.00	Sqm

No.	Item	Rate	Unit
	Providing and laying rectified Glazed Ceramic floor tiles 300x300 mm or more (having thickness 9 to 10mm) of 1st quality conforming to IS : 15622 of approved make in colours White, Ivory, Grey, Fume Red Brown, laid on 20mm thick cement mortar 1:4 (1 Cement : 4 sand) including grouting the joints with white cement and matching pigments etc., complete.		
35.	<p><b><u>S.O.R. Item No. 11.34 Page 203</u></b></p> <p>Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 sand) :</p>		
	11.34.125 mm thick.	1034.00	Sqm
36.	<p><b><u>S.O.R. Item No. 2.27 Page 26</u></b></p> <p>Supplying and filling in plinth with crusher stone dust / coarse sand under floors including, watering, ramming consolidating in layers not exceeding 20cm in depth and dressing complete.</p>	672.00	Cum
37.	<p><b><u>S.O.R. Item No. 14.27 Page 262</u></b></p> <p>Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.</p>	5.10	Sqm
38.	<p><b><u>S.O.R. Item No. 11.22 Page 201</u></b></p> <p>Providing and fixing 18mm thick gang saw cut mirror polished (premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 sand) with</p>		

No.	Item	Rate	Unit
	joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing moulding and polishing to edge to give high gloss finish wherever required etc. complete at all levels. samples approved by Engineer-in-charge.		
	11.22.1 Raj Nagar plain/White Marble/Udaipur Green Marble /Zebra black.	1797.00	Sqm
	11.22.2 Granite of any colour and shade	-	-
	11.22.3 Cuddpah stone	-	-
39.	<b><u>S.O.R. Item No. 11.23 Page 201</u></b> Extra for prefinished nosing to treads of steps of marble stone.	-	-
40.	<b><u>S.O.R. Item No. 9.3 Page 131</u></b> Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position :		
	9.3.2 Kiln seasoned and chemically treated Haldu, Kail, Bija wood.	77538.00	Cum
41.	<b><u>S.O.R. Item No. 9.6.5.3 Page 132</u></b> Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick :		
	9.6.5 Particle Board 12 mm thick		
	9.6.5.3 Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side, Grade I, Type II IS:12823 marked.	1333.00	Sqm